


Regd. Office- PSEB Head Office, The Mall Patiala- 147001. CIN- U40109PB2010SGC033813**OFFICE OF: Sr. XEN/CIVIL, PILOT WORKSHOP, MOHALI****Email- xen-pilotws-mohali@pspcl.in, Phone No. 96461-19299**

To

D.G.M./I.T.
PSPCL, Patiala
(tender@pspcl.in)**Through Email only**Memo No.: 22 /W16Date: 07 /01/2026**Subject: Upload Press-Tender Notice and NIT on PSPCL website - Tender Enquiry no-07/ PWM/2025-26 – Estimated Cost ₹ 3.88 lakhs including GST.**


Enclosed please find herewith Press-Tender Notice in both Punjabi and English along with the NIT to be uploaded on the official website of PSPCL.

| | | |
|----|-------------------------|---|
| 1. | Name of Division | Sr. Xen/Civil Pilot Workshop, PSPCL, SAS Nagar (Mohali) |
| 2. | Accounting Head | 74.2 |
| 3. | Name of Scheme | Transmission and Distribution |
| 4. | Project Provision | Exists with Chief Engineer/ Civil Design & Construction PSPCL Patiala |
| 5. | Head Account | Revenue |
| 6. | Location Code | 732 |
| 7. | Name of Accounting Unit | Sr. Xen/Civil Pilot Workshop, PSPCL, SAS Nagar (Mohali) |

DA: As above
Sr. Executive Engineer
Pilot Workshop, PSPCL
SAS Nagar (Mohali)Endst. No.: 23/24 /W16Date: 07 /01/2026

Copy of the above is forwarded to following for information please: -

1. Chief Engineer, Civil Design & Construction, PSPCL, Shakti Vihar, Patiala.
2. SE PW & MDI, PSPCL, Shakti Vihar, Patiala.


Sr. Executive Engineer
Pilot Workshop, PSPCL
SAS Nagar (Mohali)



PUNJAB STATE POWER CORPORATION LTD.

(Regd. Office PSEB Head Office, The Mall, Patiala)
Corporate Identification Number: U40109PB2010SGC033813 | Website:
www.pspcl.in

(Contact number 96461-19299)

Tender Enquiry No. 07/PWM/2025-26

Dated: 02/01/2026

Sr. Executive Engineer, Pilot Workshop, Industrial Area Phase 7, SAS Nagar Mohali, invites open tender through press for **Maintenance of Non-Residential Buildings (NRB) including Boundary wall and other maintenance civil works at Pilot Workshop SAS Nagar (Mohali) during year 2025-26**. For detailed NIT & tender specification, please refer to <https://pspcl.in> from 08/01/2026 from 03:00 PM onwards.

Note: Corrigendum and addendum, if any, will be published online at <https://pspcl.in> only.



ਪੰਜਾਬ ਰਾਜ ਪਾਵਰ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮਟਿਡ

(ਰਜਿਸਟਰਡ ਦਫਤਰ: ਪੀ.ਐਸ.ਈ.ਬੀ. ਮੁੱਖ ਦਫਤਰ, ਦੀ ਮਾਲ, ਪਟਿਆਲਾ)

ਕਾਰਪੋਰੇਟ ਪਛਾਣ ਨੰਬਰ: U40109PB2010SGC033813 | ਵੈੱਬਸਾਈਟ: www.pspcl.in


(ਸੰਪਰਕ ਨੰਬਰ 96461-19299)

ਟੈਂਡਰ ਇਨਕੁਆਰੀ ਨੰਬਰ: 07/ ਪੀ.ਡਬਲਯੂ.ਐਮ/ 2025-26

ਮਿਤੀ: 02/01/2026

ਸੀਨੀਅਰ ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ, ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ, ਇੰਡਸਟਰੀਅਲ ਏਰੀਆ ਫੇਜ਼ 7, ਐਸ.ਏ.ਐਸ. ਨਗਰ ਮੋਹਾਲੀ, ਵੱਲੋਂ ਸਾਲ 2025-26 ਦੌਰਾਨ ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਐਸ.ਏ.ਐਸ. ਨਗਰ (ਮੋਹਾਲੀ) ਵਿਖੇ ਗੈਰ-ਰਿਹਾਇਸ਼ੀ ਇਮਾਰਤਾਂ (ਐਨ.ਆਰ.ਬੀ.) ਦੇ ਰੱਖ-ਰਖਾਅ ਲਈ ਪ੍ਰੈਸ ਰਾਹੀਂ ਖੁੱਲ੍ਹਾ ਟੈਂਡਰ ਮੰਗੇ ਜਾਂਦੇ ਹਨ। ਇਸ ਕੰਮ ਦੀ DNIT ਅਤੇ ਟੈਂਡਰ ਸਪੈਸੀਫੀਕੇਸ਼ਨ ਸਬੰਧੀ ਡਿਟੇਲ ਨੋਟਿਸ <https://pspcl.in> ਦੀ ਵੈਬ-ਸਾਈਟ ਤੇ ਮਿਤੀ 08/01/2026 ਨੂੰ ਦ:ਬ 3:00 ਤੋਂ ਦੇਖੇ ਜਾ ਸਕਦੇ ਹਨ।

ਨੋਟ: ਕੋਈ ਵੀ ਸੋਧ ਅਤੇ ਵਾਧਾ ਸਬੰਧੀ ਵੇਰਵੇ ਸਿਰਫ <https://pspcl.in> ਵੇਬਸਾਈਟ ਤੇ ਹੀ ਦੇਖੇ ਜਾ ਸਕਦੇ ਹਨ।


Sr. Executive Engineer
Pilot Workshop, PSPCL, Mohali
AS


Punjab State Power Corporation Limited

Regd. Office PSEB Head Office, The Mall Patiala-147001

Corporate Identity Number: U40109PB2010SGC033813

Website: www.pspcl.in

(Office of the Sr. XEN Pilot Workshop, SAS Nagar (Mohali))

Contact: 9646119299

Email: xen-pilotws-mohali@pspcl.in

ਵੱਲ

NOTICE BOARD

 ਮੀਮੇ ਨੰ: 21 /W16 ਮਿਤੀ: - 07/01/2026.

ਵਿਸ਼ਾ:- ਪ੍ਰੈਸ ਟੈਂਡਰ ਨੋਟਿਸ - **Tender Enquiry no- 07/ PWM/ 2025-26 - Maintenance of Non-Residential Buildings (NRB) including Boundary wall and other maintenance civil works at Pilot Workshop SAS Nagar (Mohali) during year 2025-26.**

ਸ਼੍ਰੀ ਮਾਨ ਜੀ,


ਪੰਜਾਬ ਰਾਜ ਬਿਜਲੀ ਬੋਰਡ (ਹੁਣ ਪੀ.ਐਸ.ਪੀ.ਸੀ.ਐੱਲ) ਦੀ ਤਰਫ਼ੋਂ ਹੇਠ ਲਿਖੇ ਕੰਮ ਲਈ ਪੀ.ਐਸ.ਪੀ.ਸੀ.ਐੱਲ ਦੀਆਂ ਸ਼ਰਤਾਂ ਅਤੇ ਨਿਯਮਾਂ ਅਨੁਸਾਰ ਨਿਮਨ ਹਸਤਾਖਰ ਦੇ ਦਫ਼ਤਰ ਵੱਲੋਂ ਸੀਲ ਬੰਦ ਟੈਂਡਰ ਮੰਗੇ ਜਾਂਦੇ ਹਨ।

| ਲੜੀ ਨੰ | ਵੇਰਵਾ | ਅੰਦਾਜ਼ਨ ਲਾਗਤ | ਪੇਸ਼ਗੀ ਰਕਮ | ਕੰਮ ਪੂਰਾ ਕਰਨ ਦੀ ਮਿਆਦ | ਟੈਂਡਰ ਖਰੀਦਣ ਦੀ ਆਖਰੀ ਮਿਤੀ ਅਤੇ ਸਮਾਂ | ਟੈਂਡਰ ਖੋਲਣ ਦੀ ਮਿਤੀ ਅਤੇ ਸਮਾਂ |
|--------|--|--------------|-----------------|----------------------|-----------------------------------|-----------------------------|
| 1. | ਸਾਲ 2025-26 ਦੌਰਾਨ ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਐਸਏਐਸ ਨਗਰ (ਮੁਹਾਲੀ) ਵਿਖੇ ਗੈਰ-ਰਿਹਾਇਸ਼ੀ ਇਮਾਰਤਾਂ ਦੀ ਦੇਖਭਾਲ, ਜਿਸ ਵਿੱਚ ਦੀਵਾਰ ਅਤੇ ਹੋਰ ਰੱਖ-ਰਖਾਅ ਸਿਵਲ ਕਾਰਜ ਸ਼ਾਮਲ ਹਨ। (ਵੇਰਵੇ ਲਈ Annexure-A ਦੇਖੋ) | 3.88 ਲੱਖ | ਸਿਰਫ਼ 7800/-ਰੁ: | 6 ਮਹੀਨੇ | 05/02/2026 12:00 ਬ:ਦੁ: | 05/02/2026 03:00 ਬ:ਦੁ: |

ਨਿਯਮ ਅਤੇ ਸ਼ਰਤਾਂ:-

- ਜੇਕਰ ਕਿਸੇ ਕਾਰਨ ਉਕਤ ਮਿਤੀ ਨੂੰ ਛੁੱਟੀ ਹੋ ਜਾਂਦੀ ਹੈ ਤਾਂ ਇਹ ਟੈਂਡਰ ਕੰਮ ਵਾਲੇ ਅਗਲੇ ਦਿਨ ਪ੍ਰਾਪਤ ਕੀਤੇ ਅਤੇ ਖੋਲੇ ਜਾਣਗੇ।
- ਸਿਰਫ਼ ਉਹਨਾਂ ਠੇਕੇਦਾਰਾਂ ਦਾ ਟੈਂਡਰ ਸਵੀਕਾਰ ਕੀਤਾ ਜਾਵੇਗਾ ਜੋ ਰੁ: 1180/- ਸਮੇਤ GST (non-refundable) ਬਤੌਰ ਸਪੈਸੀਫਿਕੇਸ਼ਨ/ ਟੈਂਡਰ ਕੀਮਤ ਉਕਤ ਮਿਤੀ ਨੂੰ ਜਾਂ ਇਸ ਤੋਂ ਪਹਿਲਾਂ ਕਿਸੇ ਵੀ ਕੰਮ ਵਾਲੇ ਦਿਨ ਜਮਾਂ ਕਰਵਾ ਕੇ ਸਪੈਸੀਫਿਕੇਸ਼ਨ (ਟੈਂਡਰ ਡਾਕੂਮੈਂਟ) ਜਾਰੀ ਕਰਵਾਉਣ ਲਈ ਬਿਨੈ-ਪੱਤਰ ਦੇਣਗੇ।
- ਟੈਂਡਰ ਦੇਣ ਵਾਲੇ ਹੇਠ ਲਿਖੀਆਂ ਸ਼ਰਤਾਂ ਪੂਰੀਆਂ ਕਰਦੇ ਹੋਣ :-
 - ਠੇਕੇਦਾਰ, ਕੰਪਨੀ ਜਾਂ L&C society ਦੀ PWD (B&R)/ PSPCL/ PSTCL/ NTPC/ State Electricity Utilities ਅਧਾਰਿਆਂ ਵਿਚ ਸਿਵਲ ਦੇ ਕੰਮ ਕਰਨ ਲਈ ਨਾਮਜ਼ਦਗੀ ਹੋਣੀ ਲਾਜ਼ਮੀ ਹੈ।
 - ਟੈਂਡਰ ਭਰਣ ਵਾਲੇ ਦਾ EPF commissioner ਕੋਲ ਰਜਿਸਟਰ ਹੋਣਾ ਅਤੇ EPF Code ਨੰਬਰ ਹੋਣਾ ਲਾਜ਼ਮੀ ਹੈ।
 - ਟੈਂਡਰ ਭਰਣ ਵਾਲੇ ਕੋਲ PAN, EPF, GST No ਹੋਣਾ ਲਾਜ਼ਮੀ ਹੈ।

- (4) ਵਿਸਥਾਰ ਪੂਰਵਕ ਟੈਂਡਰ ਸਪੈਸੀਫਿਕੇਸ਼ਨ/ ਡਰਾਇੰਗ/ ਕੰਮ ਦਾ ਵੇਰਵਾ ਇਸ ਦਫਤਰ ਵਿੱਚ ਕੰਮ ਵਾਲੇ ਕਿਸੇ ਵੀ ਦਿਨ ਸਵੇਰੇ 9 ਵਜੇ ਤੋਂ ਸ਼ਾਮੀ 5 ਵਜੇ ਤੱਕ ਦੇਖੀ ਜਾ ਸਕਦੀ ਹੈ।
- (5) ਪੇਸ਼ਗੀ ਰਕਮ (if applicable) ਸੀਨੀਅਰ ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ, ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ, ਮੋਹਾਲੀ ਦੇ ਦਫਤਰ ਵਿੱਚ ਉਸ ਦੇ ਹੱਕ ਵਿੱਚ ਡਿਮਾਂਡ ਡਰਾਫਟ ਜੋ ਕਿ ਮੋਹਾਲੀ ਵਿੱਚ ਭੁਗਤਾਨ ਯੋਗ ਹੋਵੇ ਅਪਣੀ ਬੋਲੀ ਨਾਲ ਨੱਥੀ ਕੀਤਾ ਜਾਵੇ।
- (6) ਸ਼ਰਤਾਂ ਵਾਲਾ ਟੈਂਡਰ ਜਾਂ ਤਾਰ/ ਫੈਕਸ ਰਾਹੀਂ ਮੰਗੇ ਗਏ ਟੈਂਡਰ ਸਵੀਕਾਰ ਨਹੀਂ ਕੀਤਾ ਜਾਵੇਗਾ।
- (7) ਸਮਰਥ ਅਧਿਕਾਰੀ ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਮੋਹਾਲੀ ਜੀ ਨੂੰ ਕਿਸੇ ਵੀ ਟੈਂਡਰ ਦੇ ਜਾਂ ਸਾਰਿਆਂ ਟੈਂਡਰਾਂ ਨੂੰ ਬਿਨਾਂ ਕੋਈ ਕਾਰਨ ਦੱਸੇ ਰੱਦ ਕਰਨ ਦਾ ਹੱਕ ਹੋਵੇਗਾ।
- (8) ਟੈਂਡਰ ਖੋਲਣ ਦੀ ਮਿਤੀ ਤੱਕ ਸੀ.ਐਸ.ਆਰ ਦੇ ਸਬੰਧ ਵਿੱਚ ਜਾਰੀ ਕੀਤੀਆਂ ਸਾਰੀਆਂ ਸੋਧਾਂ ਜਿਸ ਵਿੱਚ ਏ ਅਤੇ ਸੀ ਸਲਿੱਪ ਵਜੋਂ ਸ਼ਾਮਲ ਹਨ, ਲਾਗੂ ਹੋਣਗੀਆਂ।
- (9) ਸਮਰਥ ਅਧਿਕਾਰੀ ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਮੋਹਾਲੀ ਜੀ ਵੱਲੋਂ ਟੈਂਡਰ ਵਿੱਚ ਦਰਜ ਕਾਰਜ ਆਇਟਮਾਂ ਦੇ ਮਿਕਦਾਰ ਵਿੱਚ ਕੰਮ ਦੌਰਾਨ ਵਾਧਾ ਜਾਂ ਘਾਟਾ ਕੀਤਾ ਜਾ ਸਕਦਾ ਹੈ।
- (10) ਠੇਕੇਦਾਰ ਨੂੰ ਈ.ਐਸ.ਆਈ ਐਕਟ ਅਤੇ ਈ.ਪੀ.ਐਫ ਅਤੇ ਲੇਬਰ ਐਕਟ ਦੀਆਂ ਧਾਰਾਵਾਂ ਨੂੰ ਮੰਨਣਾ ਪਵੇਗਾ ਅਤੇ ਇਹਨਾਂ ਐਕਟਾਂ ਅਧੀਨ ਹੋਣ ਵਾਲੀਆਂ ਅਦਾਇਗੀਆਂ ਕਰਨੀਆਂ ਪੈਣਗੀਆਂ।
- (11) ਟੈਂਡਰ ਖੋਲਣ ਦੀ ਮਿਤੀ ਤੋਂ 120 ਦਿਨ ਤੱਕ ਭਰੇ ਗਏ (Quoted) ਰੇਟ ਲਾਗੂ ਰਹਿਣਗੇ।
- (12) ਬਿਲ ਸਹਾਇਕ ਇੰਜੀਨੀਅਰ ਦੇ ਦਫਤਰ ਵਿੱਚ ਤੁਹਾਡੇ ਵੱਲੋਂ ਪੇਸ਼ ਕਰਨਾ ਹੋਵੇਗਾ। ਇਸ ਦੀ ਅਦਾਇਗੀ ਮੰਡਲ ਲੇਖਾ ਸੁਪਰਡੈਂਟ ਵੱਲੋਂ ਚੈਕ ਕਰਨ ਉਪਰੰਤ ਹੀ ਕੀਤੀ ਜਾਵੇਗੀ।
- (13) ਠੇਕੇਦਾਰ ਵੱਲੋਂ ਆਪਣੀ ਲੇਬਰ ਨੂੰ ਪੇਮੈਂਟ ਪੰਜਾਬ ਲੇਬਰ ਰੇਟਾਂ ਤੇ ਕਰਨੀ ਹੋਵੇਗੀ।
- (14) ਠੇਕੇਦਾਰ ਨੂੰ GST ਦੀ ਅਦਾਇਗੀ ਉਸ ਵੱਲੋਂ ਜਮ੍ਹਾਂ ਕੀਤੀ ਰਕਮ ਦੇ ਦਸਤਾਵੇਜ਼ ਪੇਸ਼ ਕਰਨ ਉਪਰੰਤ ਕੀਤੀ ਜਾਵੇਗੀ।
- (15) ਕੰਮ ਸਮੇਂ ਸਿਰ ਨਾ ਕਰਨ ਦੀ ਸੂਰਤ ਵਿੱਚ $\frac{1}{2}\%$ ਅਲਾਟਿਡ ਲਾਗਤ ਦਾ ਪ੍ਰਤੀ ਹਫਤਾ ਜਾਂ ਉਸ ਦੇ ਹਿੱਸੇ ਵਜੋਂ ਬਾਕੀ ਰਹਿੰਦੇ ਕੰਮ ਦਾ ਜੁਰਮਾਨਾ ਵਜੋਂ ਵਸੂਲ ਕੀਤਾ ਜਾਵੇਗਾ। (ਜੁਰਮਾਨੇ ਦੀ ਸਮੁੱਚੀ ਕੀਮਤ ਅਲਾਟਮੈਂਟ ਆਰਡਰ ਵਿੱਚ ਦਰਸਾਈ ਕੁਲ ਰਕਮ ਦਾ 10% ਤੋਂ ਵੱਧ ਨਹੀਂ ਹੋਵੇਗਾ)। ਵਰਕਸ਼ਾਪ ਰੈਗੂਲੇਸ਼ਨ 1997 ਦੀ ਧਾਰਾ 3.14 ਅਨੁਸਾਰ ਲਾਗੂ ਹੋਵੇਗਾ।
- (16) ਕੰਮ ਦੌਰਾਨ ਉਸਾਰੀ ਲਈ ਪੀ.ਐਸ.ਪੀ.ਐਲ ਵੱਲੋਂ ਜਾਰੀ ਸੀਮਿੰਟ ਹੀ ਵਰਤਣਾ ਲਾਜ਼ਮੀ ਹੋਵੇਗਾ।
- (17) ਟੈਂਡਰ ਦਸਤਾਵੇਜ਼ ਵਿੱਚ ਦਰਜ ਸ਼ਰਤਾਂ ਇਸ ਕੰਮ ਲਈ ਇੰਨ-ਬਿਨ ਲਾਗੂ ਹੋਣਗੀਆਂ।


 ਸੀਨੀਅਰ ਕਾ: ਕਾ: ਇੰਜੀਨੀਅਰ
 ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਮੋਹਾਲੀ

| ANNEXURE-A | | | |
|------------|---|------|-----------|
| WORK | Maintenance of Non-Residential Buildings (NRB) including Boundary wall and other maintenance civil works at Pilot Workshop SAS Nagar (Mohali) during year 2025-26 | | |
| SN | Narration | Unit | Qty |
| 1 | Dismantling brick work tile masonry or tile lining - in cement [CSR Ref- 8.5 (b)] | cum | 5.951 |
| 2 | Dismantling concrete - 1:2:4 mix [CSR Ref- 8.6 (d)] | cum | 3.357 |
| 3 | Dismantling cement conglomerate floors 25mm to 50mm thick including concrete base. [CSR Ref- 8.16] | sqm | 90.860 |
| 4 | Removing Doors and Windows (Steel or wood) with chowkhats by making recesses in walls when the wall is not to be dismantled. [CSR Ref- 8.26] | each | |
| a | Security Post window | each | 2.000 |
| b | AE bathroom door | each | 1.000 |
| 5 | Scraping cement plaster [CSR Ref- 8.31 (c)] | sqm | 93.528 |
| 6 | Scraping Bricks dismantled from brick work in lime or cement | Nos | 1,340.000 |
| 7 | 100 mm thick CC1:8:16 with stone ballast or shingle mixing by mechanical means using concrete mixer volumetric type [CSR Ref- 10.6 b(ii)] | cum | 1.104 |
| 8 | Cement Concrete 1:2:4 with stone ballast or shingle mixing by mechanical means using concrete mixer volumetric type [CSR Ref- 10.13 a (ii)] | cum | 2.942 |
| 9 | First class burnt brick work laid in cement sand mortar 1:4 in foundation and plinth. [CSR Ref- 11.7] | cum | 3.105 |
| 10 | First class burnt brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level. [CSR Ref- 11.6] | cum | 6.797 |
| 11 | Conglomerate floor 40mm thick cement concrete topping 1:2:4 using mechanical mixer for mixing of material [CSR Ref- 14.6] | sqm | 90.860 |
| 12 | 12.5mm thick cement plaster 1:4 [CSR Ref- 15.09] | sqm | 95.355 |
| 13 | White washing (First coat or subsequent one coat) | sqm | 30.868 |
| 14 | Finishing walls with exterior decorative cement-based paint such as snowcem, robbiacem etc. two coats to give an even shade. | sqm | 18.280 |
| 15 | Providing & Fixing glass panes with nails and putty or wooden strip complete in all respect (4mm thick or 10.78 Kg/ sqm) [CSR Ref- 17.26 (b) ii] | sqm | 2.131 |
| 16 | Providing and fixing 12mm thick 150mm wide pelmets with 25mm dia aluminum rod and brackets including fixing with 25mmx3mm MS Flat 10cm long and PVC Plug etc complete [CSR Ref- 17.37 (b)] | Mtr. | 40.000 |
| 17 | Fixing steel window in walls with lugs, embedded in 15cmx12cmx7.5cm of cement concrete block of 1:2:4 mix including cost of cement concrete for lugs. [CSR Ref- 18.23] | sqm | 0.935 |
| 18 | Supplying Pressed steel sheet frames (chowkhat) consisting of 18gauge (1.25 mm thick steel sheet of the specified section, including iron lugs (hold fast) iron hinges conforming to PWD specification [CSR Ref- 18.24 (b)] | m | 3.000 |
| 19 | Providing and fixing PVC Cistern 10 Ltr. Capacity ISI marked IS 7231:1994(size 32.5x47.6x15.5 cm) of approved make (to the approval of the Engineer-in-charge) including PVC fittings complete [CSR Ref- 30.6 a] | Each | 2.000 |
| 20 | Providing and fixing jet spray with 2' 6" long PVC pipe [CSR Ref- 30.8 b] | Each | 1.000 |
| 21 | Extra for providing and fixing G.I. 32mm waste pipe for urinal. [CSR Ref- 30.19 a] | Each | 2.000 |

| | | | |
|----|---|-------|---------|
| 22 | Providing & fixing in position 15 mm i/d bib cock of approved make (to the approval of Engineer-in-charge) complete in all respect. [CSR Ref- 30.65 a(vii)] | Each | 3.000 |
| 23 | Providing & fixing in position stop cock / Angle valve Male female type [CSR Ref- 30.66 a] | Each | 3.000 |
| 24 | Providing & fixing in position PVC water storage tanks triple layer make as approves by Engineer-in-Charge including hosting and carriage from store to site of work complete with providing and fixing 15mm or 20mm internal Diameter tanki nipple complete. (Excluding cost of platform). [CSR Ref- 30.97 (i)] | Litre | 500.000 |
| 25 | Painting of pelmets of Doors and window [CSR Ref- 31.20 (c)] | Each | 10.000 |
| 26 | Recovering and restuffing of sofa chair [CSR Ref- 31.23 (e)] | Each | 8.000 |
| | ELECTRICAL ITEMS | | |
| 27 | Wiring fan point without fan box in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade with step type electronic fan regulator 100watts (socket size). [CSR Ref- 34.08 a(i)] | Each | 2.000 |
| 28 | Wiring light point in PVC insulated copper conductor single core FR cable (ISI marked) overall 1.5 sq. mm, 1100volts grade. [CSR Ref- 34.08 b(ii)] | Each | 4.000 |
| 29 | Wiring call-bell point in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade with bell push and electronic buzzer 230volts AC (including the cost of bell push, electronic buzzer & powder coated concealed metal box for electronic buzzer). [CSR Ref- 34.08 b(iii)] | Each | 2.000 |
| 30 | Wiring 3 pin 16/20 amp. power plug control and switch. [CSR Ref- 34.08 b(vi)] | Each | 6.000 |
| 31 | Wiring fan point without fan box in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade with step type electronic fan regulator 100watts (socket size). [CSR Ref- 34.07 (i)] | Each | 2.000 |
| 32 | Wiring light point in PVC insulated copper conductor single core FR cable (ISI marked) overall 1.5 sq. mm, 1100volts grade. [CSR Ref- 34.07 (ii)] | Each | 10.000 |
| 33 | Wiring 3 pin 16/20 amp. power plug control and switch. [CSR Ref- 34.07 b(vi)] | Each | 6.000 |
| 34 | PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1 sq.mm, 1100volts grade [CSR Ref- 34.09 (i)] | Mtr | 20.000 |
| 35 | PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq.mm, 1100volts grade [CSR Ref- 34.09 (ii)] | Mtr | 30.000 |
| 36 | PVC insulated copper conductor single core FRLS cable (ISI marked) overall 4 sq.mm, 1100volts grade [CSR Ref- 34.09 (iv)] | Mtr | 50.000 |
| 37 | HGW conduit Pipe 20mm dia. [CSR Ref- 34.11(i)] | Mtr | 70.000 |
| 38 | HGW conduit Pipe 25mm dia. [CSR Ref- 34.11(ii)] | Mtr | 20.000 |
| 39 | 6/10amp. One Way Modular Switch (One Module) [CSR Ref- 34.15(xi)] | Each | 30.000 |
| 40 | 16/20amp. One Way Modular Switch with Indicator (One Module) [CSR Ref- 34.15(xiii)] | Each | 12.000 |
| 41 | 6amp. 2/3 Universal Modular Shuttered Socket (two Module) [CSR Ref- 34.15(xv)] | Each | 12.000 |
| 42 | 16/20amp. Universal Modular Shuttered Socket (two Module) [CSR Ref- 34.15(xvi)] | Each | 8.000 |
| 43 | Step type Modular Electronic Fan Regulator 100watts (One Module) [CSR Ref- 34.15(xviii)] | Each | 6.000 |
| 44 | Ceiling Rose (Flush Piano type) [CSR Ref- 34.15(xxvi)] | Each | 6.000 |
| 45 | Bakelite Batten Holder [CSR Ref- 34.15(xxvii)] | Each | 14.000 |

| | | | |
|----|--|-------|---------|
| 46 | LED Bulb 20W/B22 base of Crompton Greaves, Havells or equivalent make on wall [As per Market rate] | Each | 6.000 |
| 47 | Supply and erection of brown Bakelite sheet white glazed translucent backside painted 3mm thick (thickness not less than 3mm) on the existing metal box including cutting, fixing and connection of existing switches and sockets and other petty material etc. [CSR Ref- 34.15(xxxiii)] | Sq.in | 720.000 |
| 48 | Powder Coated Concealed Metal Box with Brass Lugs One/Two Module [CSR Ref- 34.15(xxxiv) a] | Each | 3.000 |
| 49 | Powder Coated Concealed Metal Box with Brass Lugs Three Module [CSR Ref- 34.15(xxxiv) b] | Each | 2.000 |
| 50 | Powder Coated Concealed Metal Box with Brass Lugs four Module [CSR Ref- 34.15(xxxiv) c] | Each | 6.000 |
| 51 | MCB Double Pole 6-32amp. (10kA, Curve-C) [CSR Ref- 34.16 a(vi)] | Each | 8.000 |
| 52 | MCB Double Pole 50, 63amp. (10kA, Curve-C) [CSR Ref- 34.16 a(viii)] | Each | 1.000 |
| 53 | SP&N Double Door Distribution Board 8 way each [CSR Ref- 34.17 (ii)] | Each | 1.000 |
| 54 | P & F of 9" dia 1440 RPM single phase Exhaust fan with louvers of make Crompton Greaves /Philips India/ Bajaj /Genelac/ Khaitan as per technical specification No. 20. [NS Item] | Each | 1.000 |
| 55 | Construction of boundary wall on existing boundary wall to raise the ht. by 2 feet (including barbed wire but excluding angles) [AOR Attached] | Mtr. | 50.000 |
| 56 | Providing and fixing GI barbed wire fencing consisting of GI steel barbed wire of 2.24mm dia (2 ply bars with 4 points) as per IS-278/1962 in 5 rows in/c all fittings such as hooks bolt 3/8"dia with check nut 10"long with GI clips of 14SWG as per drg. No 3/Job no s/Arch. - 67 & CW/DB-3202 [As per approved AOR attached] | Mtr. | 100.000 |
| 57 | Septic tank and Soakage pit as per r standard DWG no. CW/DB-3070 for 10 no's Users [As per AOR attached] | No | 1.000 |
| 58 | Construction of Inspection Chamber of Size 450mm x 450mm inside with RCC 455mm x 455mm cover and frame light duty double seal [CSR Ref- 29.60 (a)] | No | 2.000 |
| 59 | uPVC Pipe to connect septic tank and soakage pit (110mm o/d Dia.) [CSR Ref- 30.74 iii B(b)] | Mtr. | 30.000 |


Sr. Executive Engineer
Pilot Workshop, PSPCL
SAS Nagar (Mohali)
