



PUNJAB STATE POWER CORPORATION LIMITED
(PSPCL Regd. Office: PSEB Head Office, The Mall Patiala)
Corporate Identity No. U40109PB20108GC033813

Office of: Addl. S.E/TL Division, Bathinda, D-119, Thermal Colony, Bathinda

Mobile No. :- 96461-36398 e.mail id:- add.se.bti@gmail.com

Open Tender Notice

Tender Enquiry No. 22/TL BTI/2024-25

Dated 08.11.2024

Subject: Replacement of 350m of 0.15sq” conductor on first 4 no rail poles from 66kV S/S Malout Road Bathinda with 350m 0.2sq” DC on DC towers of 66kV Goniana (Bhokhra) and 66kV Dan Singh Wala line (TWL No. 92/WZ/2023-24 Annex-B)

Sealed quotations are invited from approved firms/contractors/suppliers for below mentioned works. The date of sale of tender documents will be 02.12.2024 Till 11.00 AM and the date of opening is 02.12.2024 at 11:30 AM If there happens to be a holiday, the same will be opened on the next working day in the presence of their representatives. So completed documents in all respects should reach this office on or before

<u>Name of work</u>	<u>Estimated Cost</u>	<u>Tender Fees</u>	<u>EMD</u>	<u>Date of Opening</u>
Replacement of 350m of 0.15sq” conductor on first 4 no rail poles from 66kV S/S Malout Road Bathinda with 350m 0.2sq” DC on DC towers of 66kV Goniana (Bhokhra) and 66kV Dan Singh Wala line	499246/- (GST Extra)	1180/-	2% of Estimated cost	02.12.2024

TERMS & CONDITIONS :-

1. The quotation received after due date & time will be rejected.
2. The earnest money 2% will be deposited in the shape of deposited cash receipt/BA-16 or demand draft properly pledged subject to max. Rs 500000/-Enquiry/Tenders. For tenders valuing up to Rs, 50000/- no EMD is required.
3. Tender documents containing the details of work can be obtained from this office against the payment of Rs.1000 + GST (18%) (non-refundable) in the shape of D.D In favour of A.O Accounting Cell, TL Circle PSPCL Patiala.
4. Conditional, telegraphic and incomplete quotations will be rejected.
5. The tender issuing authority reserves the right to reject any or all quotations without assigning any reason.
6. All relevant/applicable terms and conditions of works regulation of PSPCL (Amended time to time).
7. The above rates are FIRM. Income Tax, Labour Welfare fund and any other State/Central Govt.Tax shall be deducted by the department. The GST shall be paid extra as applicable rates against documentary evidence. GST shall be deposited by DDO/Contractor as per PSPCL instructions. Any other terms and conditions relating to GST or any other taxes in present/future will be applicable as per PSPCL rules and regulations.
8. All requirements regarding compliance of EPF etc of workers engaged at the site of work shall entirely of firm's liability being independent EPF number holder. EPF contribution shall be directly deposited to the EPF authorities under intimation to this office, the contractor shall himself be responsible for compliance of various provisions of EPS act 1952, if applicable, being the principle employer. All obligations arising on this account shall be his responsibility and the dept. shall have nothing do you with it. However contractor shall ensure to deposit EPF/ESI of their labour to concerned department and shall submit copies of receipted challans before release of payment.
9. The contractor shall be required to submit the copies of Challans/Clearance Certificate of EPF/GST deposited with concerned authorities and copies to AO/TL Circle PSPCL, Patiala. The contractor has to submit an undertaking relating to GST without which no payment will be released.

10. All T&P required for execution of work at site shall be arranged by the contractor
11. **TERMS OF PAYMENT** After completion of work, Ninety percent of the bill price of the contract shall be paid on the submission of bill by the contractor to concerned Sr. Xen/Addl SE. The payment shall be made by AO/ TL, Circle. PSPCL Patiala after verification approval by concerned SDO/ Xen. Balance 10% shall be paid within 30 days of commissioning and taking over of transmission line and recording/checking of measurement of work done. The contractor shall furnish a performance security of amount equal to 5% value of the contract price which will be Deducted from the running bills as well as final bills also submitted by the contractor. The security furnished shall be valid initially till the expiry of defects liability period of 12 months and shall be extended appropriately as defects liability period is extended. No interest shall be paid for the security amount. On faithful execution of contractor in all respect including warranty/defect liability period, the security shall be refunded. In the event of default on the part of contractor in faithful execution of the contract, the security shall be forfeited. The forfeiture of security deposit shall be without prejudice to any other rights arising or accruing to the department under relevant provisions of the contract like Penalty/Damage due to delay in delivery or risk execution of work including suspension of business dealings with the department for a specific period.
12. **Taxes:**
Instructions issued for income tax/GST as amended from time to time by Govt. along with surcharge shall be applicable. The dedications at source shall be made as per the provisions as applicable from time to time.
13. **Completion Period:**
The time allowed for the completion of work will be 45 days from the date of intimation of readiness by the department.
14. **Penalty**
If the contractor fails to complete the work within the stipulated completion period, he shall be liable to pay penalty an amount equal to half percent of estimated cost of the whole work as shown in the contract for every week, the work remains unfinished after the contract completion period, provided always that the entire amount of compensation to be paid under the provisions of this clause shall not exceed 10% of the estimated or actual cost of work whichever is higher.
15. **Extension in completion period:**
If the contractor wants extension in completion period, he shall apply in writing to the addl. superintending engineer, TL division Bathinda stating the reason for delay on account of which he desires such extension. The competent authority can extend the completion period, if considered reasonable after getting the case pre-checked and if the delay is genuine.
16. **Scope of work**
The Quantity of work can be increased or decreased by \pm 35% with the prior approval of competent authority. No claim on this account shall be entertained. Payment of actual quantities of work executed shall be made.
17. **Others:**
 1. The work shall be executed strictly as per Terms & conditions specified in the Detailed NIT/Specifications, Relevant Drawings with their latest revisions from time to time which forms part of Contract Agreement-cum- Allotment Order
 2. If the contract neglects to execute the work or refuse to comply with orders given in writing by the engineer-in-charge in connection with the work or contravene any of the condition of allotment letter, Engineer-in-charge shall be at liberty to terminate the work and suspend the business dealing with the contractor.
18. All civil suits relating to this notice inviting tender are subject to the jurisdiction of local courts of Bathinda.

-sd-
Addl.SE/TL Division
PSPCL, Bathinda

**Replacement of 350m of 0.15sq” conductor on first 4 no rail poles from 66kV S/S Malout Road
Bathinda with 350m 0.2sq” DC on DC towers of 66kV Goniana and 66kV Dan Singh Wala line**

Scope of Work

Sr. No.	Description of Work	Qty.	Unit	Rate	Amount
1	2	3	4	5	6
1	Laying of foundations for erecting of tower of 66kv Line on Labour rates Lump-Sum basis as per PSPCL drawings including excavation, placement of steel reinforcement, concreting, stub setting, form work, centering, shoring, shuttering, back filling and other allied works required for setting stubs including the cost of sand and gravel complete in all respects as per PWD specifications crusher & sand to be arranged by the contractor. All other material i.e.Cement, TMT Steel, Stub Setting templates etc. shall be provided by PSPCL from its stores at Bathinda,Verpal and Gobindgarh free of Cost.				
(i)	Tower Type-B (D-30 Deg.) + 3/6 mtr Ext.Open Type (CW/TT-3012R2) (6 Mtr Ext = 1 No.)	1	No.		
(ii)	Tower Type-C (D-60 deg.) Open type (cw/tt-3013R3) (3 mtr ext = 1 no.)	3	No.		
2	Transportation and erection of towers complete with all fittings including tack welding (Welding Rods to be supplied by the contractor) & zinc rich paint touching wherever required (zinc paint to be supplied by the contractor) Installation of danger plates, No. plates, Face Plates, Ckt Plates, Bird guard & Anti climbing devices etc on labour rate basis. (66 kV Line)	15.523	MT		
3	Transportation, Installation of Insulator Strings complete with hardware installation & Stringing & sagging of conductor 0.2sq” including fixing of cond. Accessories for the 66kv S/C line on D/C towers on labour rates basis.	0.398	CKT KM		
4	Transportation, installation, Stringing & Sagging of Earth wire 7/2.24mm at the top of tower including fixing of earth wire accessories as on labour rate basis.	0.398	KM		
5	Pit marking Angle Tower	4	No.		
6	Extra carriage and difference of rates (Civil material)	AOR			
7	Dismantlement of HRP	2	No.		
8	Dismantlement of 5RP	1	No.		
9	Dismantlement of 6RP	1	No.		
10	Dismantlement of 0.15sq” conductor DC line	0.382	Ckt km		
	Total in Rs. and In Words				

GST Payable Extra

-sd-
Addl.SE/TL Division
PSPCL, Bathinda