



ਵਣਜ਼ ਗਸ਼ਤੀ ਪੱਤਰ ਨੰ: 48/2013

To

ਸਾਰੇ ਇੰਜਨੀਅਰ-ਇਨ-ਚੀਫ/ਮੁੱਖ ਇੰਜਨੀਅਰਜ਼ / ਵੰਡ
ਅਧੀਨ ਪੰਜਾਬ ਸਟੇਟ ਪਾਵਰ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮਿਟਿਡ।

Memo No. 885/89 /DD/SR-27

Dated: 1/11/2013

Sub: Shifting of lines/ poles during road construction etc.

In order to avoid any delay at PSPCL end in shifting of lines and poles even after the requisite charges have been deposited by the applicant due to shortage of manpower / labour in all the subdivisions, PSPCL has decided to implement the following scheme/procedure in respect of National Highways/ State Highways, which may be read as Clause 40.5 of ESIM:-

40.5 Shifting of lines/ poles during road construction in respect of National Highways/ State Highways

Applicants, after approval of estimate from PSPCL, shall carry out the shifting of PSPCL lines/poles, transformers etc at their own level under the supervision of PSPCL subject to the following conditions:-

- A) Both material & labour are to be arranged by the applicant.
- B) The estimate for erection of new line with new material will be prepared by PSPCL at the cost of applicant and got sanctioned from the competent authorities. Applicant will be charged Supervision charges @ 27% of the total cost of estimate i.e. cost of material and labour etc. The Supervision charges includes the following elements:
 - i. Material inspection at firms premises and reinspection in case of failure,(if required).
 - ii. Material accountability and clearance at site.
 - iii. Supervision at the time of erection of new line and dismantlement of old line.
 - iv. Quality assurance of work.
 - v. Day to day monitoring by field staff.

Applicant will first erect the new line and after energization, the existing/old line shall be dismantled. The dismantled material, as per

Contd...2

sanctioned estimate, shall be returned to the respective store of PSPCL through concerned JE incharge under the Supervision of AE/AEE. Concerned AE/AEE/JE incharge will ensure that the dismantled material is complete in all respects and in proper condition i.e. conductor is properly rolled, poles are intact etc. To account for the cost of dismantled material, for giving credit to the applicant, the depreciated cost or residual value of dismantled material, whichever is higher but not less than 10% of the present value of new material shall be considered.

The material shall be procured from the approved suppliers of PSPCL as per PSPCL specifications and material will be inspected at manufacturer works by the officers of PSPCL and at site material will be inspected by ASE/Sr.Xen/Ds and ASE/Sr.Xen/Technical Audit concerned.


List of approved suppliers shall be given to the applicant. The applicant shall be at liberty to purchase material from any of approved suppliers of PSPCL as per design and approved specifications of PSPCL. PSPCL will arrange power shut downs if so required for shifting of lines.

- C) All the required clearances such as clearance from railway, forest department, clearance from Municipal Corporation / PUDA / Local authority, road clearance etc. shall be obtained by the applicant concerned.
- D) Construction/erection of line/system shall be carried out as per Standardization Instructions approved by PSPCL.
- E) Incidentally, if any accident/miss-happening occurs during the erection of new line/dismantlement of existing line, the entire responsibility shall lie with the applicant.
- F) Applicant shall submit Bank Guarantee of the amount equivalent to the cost of material to be dismantled, calculated at 50% of the PSPCL stock issue rates, in lieu of security for the material likely to be dismantled. This Bank Guarantee will be released to the applicant on receipt of the material in respective stores. In case applicant fails to return the dismantled material in the respective store, the Bank Guarantee deposited by the consumer / applicant shall be encashed accordingly.
- G) Applicant shall be responsible for defending all the court cases/legal complications which may arise at the time of erection of new line/ dismantlement of existing line. PSPCL will not be responsible for any loss or delay on account of Court case or due to any other reason.
- H) After completion of work and clearance from the Chief Electrical Inspector, the line shall be properly handed over to PSPCL and these lines alongwith allied material shall be the property of PSPCL.

The above scheme shall be applicable only to National Highways/ State Highways.

This issues with the approval of competent authority.

Meticulous compliance of the above may be ensured by all the field officers.



SE/Sales-I
PSPCL, Patiala.

ਪਿੱਠ ਅੰਕ ਨੰ./ 890/925 DD/SR -27

ਮਿਤੀ: 1/11/2013

ਉਪਰੋਕਤ ਦਾ ਉਤਾਰਾ ਹੇਠ ਲਿਖਿਆਂ ਨੂੰ ਸੂਚਨਾ ਅਤੇ ਲੋੜੀਂਦੀ ਕਾਰਵਾਈ ਲਈ ਭੇਜਿਆ ਜਾਂਦਾ ਹੈ:-

1. ਚੇਅਰਮੈਨ-ਕਮ-ਮੈਨੇਜਿੰਗ ਡਾਇਰੈਕਟਰ, ਪੰਜਾਬ ਰਾਜ ਪਾਵਰ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮ, ਪਟਿਆਲਾ।
2. ਸਾਰੇ ਨਿਰਦੇਸ਼ਕ, ਪੰਜਾਬ ਰਾਜ ਪਾਵਰ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮ, ਪਟਿਆਲਾ।
3. ਵਿੱਤ ਕਮਿਸ਼ਨਰ/ਫਾਇਨਾਨਸ ਟੂ ਗੇਰਮਿੰਟ ਪੰਜਾਬ ਐਕਸ ਆਫੀਸੋ ਮੈਂਬਰ, ਪੀ.ਐਸ.ਈ.ਆਰ.ਸੀ, ਚੰਡੀਗੜ੍ਹ।
4. ਸਕੱਤਰ/ ਬਿਜਲੀ ਵਿਭਾਗ, ਪੰਜਾਬ ਸਰਕਾਰ, ਚੰਡੀਗੜ੍ਹ।
5. ਸਕੱਤਰ, ਪੰਜਾਬ ਸਰਕਾਰ/ਇੰਡ: ਅਤੇ ਕਾਮਰਸ ਵਿਭਾਗ, ਪੰਜਾਬ ਸਰਕਾਰ, ਚੰਡੀਗੜ੍ਹ।
6. ਪ੍ਰੋਜੈਕਟ, ਸਟੇਟ ਡਿਸਟ੍ਰਿਬਿਊਟਿਡ ਰਿਫਰੈਸਲ ਕਮਿਸ਼ਨ (ਪੰਜਾਬ) SCQ ਨੰ: 3009-10, Sec-22, ਚੰਡੀਗੜ੍ਹ।
7. ਮੁੱਖ ਇੰਜੀਨੀਅਰ/ ਚੇਅਰਮੈਨ (ਫੋਰਮ), ਪੀ.-1, ਵਾਈਟ ਹਾਊਸ, ਰਾਜਪੁਰਾ ਕਲੋਨੀ, ਪਟਿਆਲਾ।
8. ਸਕੱਤਰ, ਪੰਜਾਬ ਰਾਜ ਬਿਜਲੀ ਰੈਗੂਲੇਟਰੀ ਕਮਿਸ਼ਨ, SCO.ਨੰ: 220-221, ਸੈਕਟਰ-34 ਏ, ਚੰਡੀਗੜ੍ਹ।
9. Ombudsman, Electricity Punjab 66 KV Grid Sub Stn., Plot no. A-2, Industrial Area, Phase-1, SAS Nagar (Mohali)-160055
10. ਨਿੱਜੀ ਸਕੱਤਰ ਟੂ ਬਿਜਲੀ ਮੰਤਰੀ, ਪੰਜਾਬ ਸਿਵਲ ਸਕੱਤਰੇਤ ਪੰਜਾਬ ਸਰਕਾਰ ਚੰਡੀਗੜ੍ਹ।
11. ਚੀਫ ਕੋ-ਆਰਡੀਨੇਟਰ, ਉਦਯੋਗ ਸਹਾਇਕ ਡਾਇਰੈਕਟਰ ਆਫ ਇੰਡੀਸਟਰੀਜ਼ ਪੰਜਾਬ Sec-17, ਚੰਡੀਗੜ੍ਹ।
12. Chief Administration & IR, PSPCL. Patiala.
13. ਮੁੱਖ ਬਿਜਲੀ ਇੰਸਪੈਕਟਰ, ਪੰਜਾਬ ਸਰਕਾਰ, ਪਟਿਆਲਾ।
14. Chief Auditor, PSPCL, Patiala.
15. Chief Engineer / ARR & TR, PSPCL, Patiala.
16. ਐਸ.ਈ. / ਆਈ.ਟੀ., ਪੀ.ਐਸ.ਪੀ.ਸੀ.ਐਲ., ਪਟਿਆਲਾ ਨੂੰ ਪੀ.ਐਸ.ਪੀ.ਸੀ.ਐਲ. ਦੀ ਵੈਬ ਸਾਈਟ ਤੇ ਅਪਲੋਡ ਕਰਨ ਹਿੱਤ।
17. Dy.CE/Sales-1, Dy.CE/Sales-2 and Dy.CE/Billing, PSPCL
18. All Addl SEs / Sr Xens / AEEs under Commercial organization, PSPCL.
19. Under Secy/Meetings with reference to his U.O No 3113/BOD-30.20/2013/PSPCL dated 26/9/13.


ਵਪੀਕ ਡਿਜੀਟਿਜ਼/ਐਸ.ਆਰ,
ਵਾ: ਮੁੱਖ ਇੰਜੀਨੀਅਰ/ਵਟਨੁ,
ਪੀ.ਐਸ.ਪੀ.ਸੀ.ਐਲ., ਪਟਿਆਲਾ।